

# SURVEY & REMONUMENTATION

FEB 21 2001

## SECTION

### LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Iron	Located In:	Corner Code #
(County)		
1. Public Land Survey	T <u>43N</u> R <u>R31W</u>	<u>E-8</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

COMMENCING YEAR 2000  
RECEIVED FOR RECORD  
IRON COUNTY, MICHIGAN

00 DEC 22 PM 3: 25

*L.C. Records: L. 8, P. 310*

*Gary L. Pisoni*  
REGISTERED LAND SURVEYOR

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

Quarter Corner Between Sections 20 and 21, T43N, R31W

I, Gary L. Pisoni, in a field survey on December 5, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5			4		3			2	1
3													
4	7						8		9			10	11
5													
6	18						17		16			15	14
7													
8	19						20		21			22	23
9													
10	30						29		28			27	26
11													
12	31						32		33			34	35
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established on July 17, 1849 by John Burt, U.S. Deputy Surveyor.

Original Corner; Cedar Post

Original Bearing Trees:

Cedar	10"	N 35° W	15 links (9.90 feet)
Cedar	8"	S 37° E	12 links (7.92 feet)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of original B.T.s found.

Found a location tag which bears N 71° 09' E, 51.1 feet from quarter corner.

Restored the corner position by single proportionate measurement and on line between the Northwest and Southwest Section corners of Section 21.

Corner record research on file with County Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position, set a 5/8" diameter by 30" long rebar pin with a 3" diameter aluminum cap stamped as follows: Iron County Remonumentation, T43N, R31W, 1/4, S-20, S-21, 2000, RLS 27457 from which I established the following new blazed and scribed bearing trees: (all measurements taken to a nail in side of tree)

Popple	8"	N 31° E	17.88 feet
Balsam	5"	S 76° E	14.29 feet
Popple	8"	S 41° E	4.87 feet
Popple	7"	S 85° W	20.18 feet
Steel sign post		N 75° E	0.6 feet

PEER GROUP APPROVED  
*Gary L. Pisoni 12-19-2000*  
COUNTY REPRESENTATIVE

00-078

Signed by Gary L. Pisoni

Date 12-19-2000

Surveyor's Michigan License No. 27457

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983  
REVISED OCT., 1995

