

SURVEY & REMONUMENTATION

FEB 21 2001

COMMENCING YEAR 2000
RECEIVED FOR RECORD
IRON COUNTY, MICHIGAN

00 DEC -5 PM 12: 50

L.C. Records: L.S., P. 216

Robert A. Goodreau
REGISTERED PROFESSIONAL SURVEYOR

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Iron	Located In:	Corner Code #
(County)		
1. Public Land Survey	T <u>43N</u> R <u>31W</u>	<u>I-11</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Robert A. Goodreau in a field survey on May 10, 2000, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-11 Original corner established by John Burt, U.S. Deputy Surveyor, on 23 July 1849.

Original witnesses: Fir 8 N68E 13 links
Y. Birch 14 S20W 19 links

Brian R. Taavola RLS replaced a found nail (as per info from R. Perkins survey notes) w/ a 5/8" copper clad rod w/ yellow plastic cap stamped MDOT 21583 in monument box on 25 May 1988 (Liber 6, Page 236).

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-11 Found corner as described by Taavola.

Found witness recorded by Taavola as: S 68 E 103.61' 15" Red Pine

Corner record research on file with county representative.


PEER GROUP APPROVED
Iron County Rep. 11/1/2000
COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-11 Accepted corner as found.

Witnesses: 17" Red Pine S 68 E 103.61'
16" Balsam Fir S 02 W 95.70'
Power pole #98-12680 N 10 W 91.21'
Reference monument (5/8" bar w/ cap) South 37.08' w/sign post 1' south

Note: Measurements taken to a nail in side of witnesses.



Signed by *Robert A. Goodreau*
Surveyor's Michigan License No. 43053

Date July 1, 2000