

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Iron		Located In:		Corner Code #	
_____	(County)				
1. Public Land Survey		T	R	_____	
		T	R	_____	
		T	R	_____	
		T	R	_____	
2. Property Controlling in Section	S <u>8</u>	T <u>43N</u>	R <u>31W</u>	_____	<u>7</u>
	S	T	R	_____	
3. Miscellaneous Property in Sec.	S	T	R	_____	
	S	T	R	_____	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Feb 05 2002

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5		4		3		2		1		
3												
4	7	8		9		10		11		12		
5												
6	18	17		16		15		14		13		
7												
8	19	20		21		22		23		24		
9												
10	30	29		28		27		26		25		
11												
12	31	32		33		34		35		36		
13												

A. Description of original monument and accessories and/or subsequent restoration:
 North 1/16 corner between Sections 8 and 9. Established in 1974 by A.O. Enger, RLS on line between 1/4 corner 20.273 ch. South and Section Corner 20.272 ch. North. 1" IDx 36" iron pipe with 3.5" dia. aluminum cap. Tamarack 5 N75E 50.7', W. Pine 5 N49W 16.2'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Recovered the 1974 monument in poor condition, bent and with broken cap, apparently damaged by heavy equipment. Remonumented the corner at the position of the base of the damaged monument and in accord with the remaining 1974 NBT W. Pine, now a stump of about 5" dia. Measured check distance north approx. 1338' to Section corner, a Wisconsin-Michigan Power Co. monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 1" IDx 32" I. Pipe with 4" alum. MDNR cap. Blazed and scribed the following new bearing trees:
 6" W. Spruce N56E 48.4' "1/16S NBT"
 4" W. Spruce S05E 26.6' do
 4" W. Spruce S51W 20.7' do
 12" W. Spruce N09W 28.1' do
 Placed sq'd cedar post adjacent.
 Bearings are magnetic. Distances are to notch in lower blaze.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 2/7/02

For the Michigan Department of Natural Resources - Office of Property Management