

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Iron
 (County)

Located in: Corner Code #

- | | | | | |
|------------------------------------|---|-------------|------------|-----------|
| 1. Public Land Survey | T | <u>43</u> R | <u>31W</u> | <u>87</u> |
| | T | _____R | _____ | _____ |
| | T | _____R | _____ | _____ |
| | T | _____R | _____ | _____ |
| 2. Property Controlling in Section | S | _____T | _____R | _____ |
| | S | _____T | _____R | _____ |
| 3. Miscellaneous Property in Sec. | S | _____T | _____R | _____ |
| | S | _____T | _____R | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Jan 16 2002

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7	●											
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 (B7) Quarter corner common to Sections 18 and 19. 1849: Established by John Burt: East between 18 & 19...39.70 Set cedar qr Section post. Cedar 8 N40W 29, Fir 10 S12E 30. 41.00 Desc ledge 40 feet CNE, 42.00 Foot of do and ent swamp NW...79.70 Sect. corner. 1960: Monumented by B.D.Buckler RLS. "This corner was replaced at old squared wood post set by unknown surveyor. Corner lies on NE side of rock knob and in line with road to East". 1" pipe with 4" brass cap. 7" Cedar N8W 52.5 links, 6" Maple S38W 5.5 links. 1974: Buckler's monument found by A.O.Enger RLS and used to remonument the NE corner of Section 19 (C7).

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(B7) Original post and accessories were not found. Found the Buckler monument in good condition but did not accept it for the corner position. The position of the monument is not in accord with the original record, the 1974 Enger survey, nor the East 1/16 corner btwn Sec. 18 & 19 as described on the unrecorded plat of "Ferry and Calhoun's Village of Mansfield". I reestablished the corner in the centerline, produced, of an old E-W road, and in accord with the plat, 2647 feet, extrapolated from the section line, dimension appearing on the plat, west of the 1974 C7 monument. From this reestablished position, the GLO ledge calls check well. In 1974, A.O.Enger, in a survey described thoroughly in Liber 1 of surveys, Pages 10-20, established C7 2647' east of the 1960 monument. However, the 1974 survey contained a calculation error which resulted in Enger monumenting C7 only 2597.8' East. Fortunately, in an admittedly unlikely happenstance, the calculation error led Mr. Enger directly to the proper position for C7. His position, so computed and monumented, is, in fact, in accord with both the nearby monumented and occupied remains of the noted plat and with the nearby government corners and thus is unaffected by the discovery of the 1974 error. I found the 87 1960 monument 49.16' east of the reestablished position and on the section line, destroyed it, and defaced its accessories.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(B7) Set 1"IDx32" I. Pipe with 4" dia. alum MDNR cap. Blazed and scribed:
 8" Cedar N58E 54.6' "1/4S NBT"
 12" Maple in clump S61E 19.0' do
 8" Maple S51W 73.8' do
 5" Maple in clump N30W 14.5' do
 Bearings are magnetic. Distances to notch in lower blaze. Placed sq'd cedar post adjacent.



Signed by Stephan J. Szyszkoski Date 2/19/02
 Surveyor's Michigan License No. 33936