

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Iron</u> (County)	Located In:	Corner Code #	
1. Public Land Survey	T ___ R ___	_____	_____
	T ___ R ___	_____	_____
	T ___ R ___	_____	_____
	T ___ R ___	_____	_____
2. Property Controlling in Section	S <u>2</u> T43N R 31W	_____	9
	S <u>3</u> T43N R 31W	_____	12
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____	_____
	S ___ T ___ R ___	_____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Jul 10 2002

I, Stephan J. Szyszkoski, in a field survey on _____, 20__ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3								●					
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:
 (9-Sec. 2) East 1/16 corner, Section 2. Not established in the original survey.
 (12-Sec. 3) South 1/16 corner, Section 3. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(9-Sec. 2) Established the corner midway and on a straight line between Quarter corner and Center of Section 1317.68' east and west.
 (12-Sec. 3) Established the corner midway and on a straight line between Center of Section and Quarter corners 1322.06' north and south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(9) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Blazed and scribed: 7" B.Ash N14E 27.7' "1/16S BT" 11" Y.Birch S68E 19.7' do 9" Cedar S06W 30.7' do 8" B.Ash S79W 20.1' do Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to notch in lower blaze.	(12) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Blazed and scribed: 4" Spruce N65E 49.0' "1/16S BT" 8" Maple S33E 46.4' do 8" Maple S41W 41.4' do 11" Maple N87W 25.5' do Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to notch in lower blaze.
---	---



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 7/24/02