

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Iron	Located In:	Corner Code #
<small>(County)</small>		
1. Public Land Survey	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S <u>3</u> T <u>43N</u> R <u>31W</u>	<u>13</u>
	S <u>3</u> T <u>43N</u> R <u>31W</u>	<u>9</u>
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Jul 08 2002

I, Stephan J. Szyszkoski, in a field survey on _____, 20__ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3	●	2		1	
3								●					
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:
 (13-Sec. 3) Southeast 1/16 corner, Section 3. Not established in the original survey. Found no subsequent record.
 (9-Sec. 3) East 1/16 corner, Section 3. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(13-Sec. 3) Established the corner at the intersection of straight lines connecting opposite 1/16 corners. From the corner thus established, I found a 1"ID iron pipe, placed by persons unknown, West 26.3' distant, which I did not accept for the corner. Drove the 1"IP to flush with the ground surface.
 (9-Sec. 3) Established the corner midway and on a straight line between Center of Section and Quarter corners 1326.20' west and east.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(13) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Blazed and scribed: 4" Aspen N05E 9.0' "1/16S BT" 13" W.Spruce S40E 45.2' do 10" Maple S09W 72.7' do 4" Aspen S88W 16.9' do Set sq'd cedar post adjacent. Bearings are magnetic. Distances are notch in lower blaze.	(9) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Blazed and scribed: 6" Cedar N38E 40.0' "1/16S BT" 7" W.Spruce S74E 37.6' do 8" W.Spruce S70W 26.4' do 6" Cedar N03W 53.6' do Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to notch in lower blaze.
--	--



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 7/24/02