

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Iron
 (County)

Located In: Corner Code #

| | | |
|------------------------------------|-----------------|----|
| 1. Public Land Survey | T 43N R 31W | H2 |
| | T R | |
| | T R | |
| | T R | |
| 2. Property Controlling in Section | S 2 T 43N R 31W | 15 |
| | S T R | |
| 3. Miscellaneous Property in Sec. | S T R | |
| | S T R | |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

H2 Jul 08 2002
 15 Jul 03 2002

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

| | | | | | | | | | | | | | |
|----|---|----|---|----|---|----|---|----|---|----|---|----|---|
| 1 | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 2 | | 6 | | 5 | | 4 | | ● | | 2 | | | 1 |
| 3 | | | | | | | | | ● | | | | |
| 4 | | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | |
| 5 | | | | | | | | | | | | | |
| 6 | | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | |
| 7 | | | | | | | | | | | | | |
| 8 | | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | |
| 9 | | | | | | | | | | | | | |
| 10 | | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | |
| 11 | | | | | | | | | | | | | |
| 12 | | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | |
| 13 | | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:
 (H2) Center of Section 3. Not established in the original survey.
 (15-Sec. 2) West 1/16 corner between Sections 2 & 11. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 (H2) Established the corner at the intersection of straight lines connecting opposite 1/4 corners.
 (15-Sec. 2) Established the corner midway and at mean true bearing between Section and Quarter corners 1317.96' west and east.

| | |
|--|---|
| C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: | |
| (H2) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Blazed and scribed: 6" B.Spruce S42E 13.2' "C1/4 BT" 7" B.Spruce S23W 10.0' do 11" Maple N59W 43.0' do 9" Maple N10W 9.4' do Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to notch in lower blaze. | (15) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Blazed and scribed: 6" Sugar N37W 62.8' "1/16S BT" 4" Sugar S75E 20.2' do 4" Sugar S48E 22.3' do 6" Sugar S87W 45.0' do Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to notch in lower blaze. |



Signed by Stephan J. Szyszkoski Date 7/24/02
 Surveyor's Michigan License No. 33986