

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Iron</u> (County)	Located In:	Corner Code #	
1. Public Land Survey	T <u>43N</u> R <u>31W</u>	<u>J2</u>	
	T _____ R _____	_____	
	T _____ R _____	_____	
	T _____ R _____	_____	
2. Property Controlling in Section	S <u>2</u> T <u>43N</u> R <u>31W</u>	<u>10</u>	
	S _____ T _____ R _____	_____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

J2 Jul 03 2002
 10 Jul 02 2002

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		●				1
3									●				
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:
 (J2) Center of Section 2. Not established in the original survey.
 (10-Sec. 2) South 1/16 corner between Sections 2 & 3. Not established in the original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 (J2) Established the corner at the intersection of straight lines connecting opposite 1/4 corners.
 (10-Sec. 2) Established the corner midway and on line between Section corner 1329.50' south and Quarter corner 1329.50' north. From the position thus established, I found a 1/2" dia. iron pipe, set by persons unknown, S66E 19.2' distant, which I did not accept for the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 (J2) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Blazed and scribed:
 8" Maple S32E 19.3' "C1/4 BT"
 8" Maple in clump S03E 46.1' do
 11" Maple S27W 48.2' do
 3" Sugar S61W 14.8' do
 Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to notch in lower blaze.
 (10) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Blazed and scribed:
 5" Sugar N86E 30.8' "1/16S BT"
 8" Sugar S03E 31.7' do
 9" Sugar S39W 8.4' do
 6" Basswood N41W 22.2' do
 Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to notch in lower blaze.



Signed by Stephan J. Szyszkoski Date 7/24/02
 Surveyor's Michigan License No. 33986