

**SURVEY & REMONUMENTATION**

**FEB 21 2001**

**SECTION**

COMMENCING YEAR 2000  
RECEIVED FOR RECORD  
IRON COUNTY, MICHIGAN

00 DEC -5 PM 12: 50  
*L. C. Register: L. S., P. 214*  
*Robert A. Goodreau*  
REGISTERED PROFESSIONAL SURVEYOR

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Iron _____ (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>43N</u> R <u>31W</u>	<u>E-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Robert A. Goodreau in a field survey on March 22, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-7 Original corner established by John Burt, U.S. Deputy Surveyor, on 17 July 1849.  
Original Corner: Y. Birch post

Original witnesses: Cedar 8 N 12° W 19 links  
Cedar 12 S 41° E 28 links

Arthur O. Enger RLS replaced an old down and rotted square cedar post with a 1" ID x 36" iron pipe w/3.5" aluminum cap on 26 April 1974 (Liber 1, Page 393-394).

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-7 Found corner as described by Enger.

Found witnesses recorded by Enger as: Red Maple 9 N 63° E 27.0' "S16, NBT"  
Cedar 6 S 37° W 61.7' "S20, NBT"  
Ironwood 5 (1 of clump of 3) S 34° E 47.4' "S21, NBT"

Corner record research on file with county representative.

PEER GROUP APPROVED  
*Ray S. Person 11-14-2000*  
COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-7 Accepted corner as found.

Witnesses: Set 16d nails in above bearing trees at recorded distances.  
30" W. Birch North 3.00'  
Sign post West 1.0'

Note: Measurements taken to a nail in side of witnesses.

Signed by *RA. Goodreau*  
Surveyor's Michigan License No. 43053

Date July 1, 2000

