

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

<u>Iron</u> (County)	Located In:	Corner Code #	
1. Public Land Survey	T ___ R ___	_____	
	T ___ R ___	_____	
	T ___ R ___	_____	
	S ___ T ___	_____	
2. Property Controlling in Section	S 14 T 43N R 31W	8	
	S 14 T 43N R 31W	12	
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____	
	S ___ T ___ R ___	_____	

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims

12 Apr 04 2005  
 8 Mar 29 2005

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 20\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

(8-Sec. 14) West 1/16 corner, Section 14. Not established in the original survey.  
 (12-Sec. 14) South 1/16 corner, Section 14. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(8-Sec. 14) Established the corner midway and on a straight line between Center of Section 1322.70' East and Quarter corner 1322.70' West.  
 (12-Sec. 14) Established the corner midway and on a straight line between Center of Section 1327.28' North and Quarter corner 1327.28' South.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(8) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nails in: 9" Spruce N05E 10.8' mrkd "1/16S BT" 7" Spruce N85E 24.9' do 13" Cedar S26E 65.3' do 8" Cedar S03W 55.6' do	(12) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nails in: 11" R.Maple N82E 42.4' mrkd "1/16S BT" 5" Sugar S30E 23.3' do 4" Sugar S07W 13.0' do 3" Sugar in clump N86W 42.2' do
Bearings are magnetic. Distances are to nail with tag.	Set cedar post adjacent. Bearings are magnetic. Distances are to nail with tag.



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 4/05/05

For the Michigan Department of Natural Resources, Office of Land and Facilities