

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in \_\_\_\_\_

<u>Iron</u> (County)	Located In:	Corner Code #	
1. Public Land Survey	T _____ R _____	_____	_____
	T _____ R _____	_____	_____
	T _____ R _____	_____	_____
2. Property Controlling in Section	S 19 T 43N R 31W	_____	8
	S 19 T 43N R 31W	_____	6
	S _____ T _____ R _____	_____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	_____
	S _____ T _____ R _____	_____	_____
4. Lot No. _____, Recorded Plat _____			
5. Private Claims _____			

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 8 04/19/2010 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(8-Sec. 19) West 1/16 corner, Section 19. Not established in the original survey.

(6-Sec. 19) Northeast 1/16 corner, Section 19. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(8-Sec. 19) Established the corner on a straight line between Center of Section 19 1336.51' east and Quarter corner 1316.46' west, being 20 chains, proportionate to the original plat, west of the Center of the Section.

(6-Sec. 19) Established the corner at the intersection of straight lines connecting opposite 1/16 corners. The corner falls in an old flooding. Trees nearby are dead.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(8) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:  
 9" Cedar N03E 25.2' mrkd "1/16S BT"  
 6" Cedar S56E 1.6' do  
 7" Cedar S54W 16.2' do  
 12" Cedar N50W 2.4' do  
 Set cedar post adjacent. Bearings magnetic.

(6) Set 1"IDx32" I.pipe w/4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:  
 6" Cedar S86E 128.4' mrkd "1/16S BT"  
 9" Cedar S75E 173.5' do  
 8" dead Cedar S81W 56.8'  
 Set cedar post adjacent. Bearings magnetic.

Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 05/03/2010



For the Michigan Department of Natural Resources and Environment, Forest Management Division