

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Iron (County)	Located In:	Corner Code #
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S 19 T 43N R 31W _____	10
	S 30 T 43N R 31W _____	3
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims	10 04/20/2010	
	3 04/20/2010	

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 3 04/20/2010 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(10-Sec. 19) South 1/16 corner between Sections 19 T43N-R31W and 24 T43N-R32W. Not established in the original survey.

(3-Sec. 30) North 1/16 corner between Section 30 T43N-R31W and Section 25 T43N-R32W. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(10-Sec. 19) Established the corner midway and on the Range line between Section corner 1318.90' south and Quarter corner 1318.90' north. An E-W gravel road passes 18' north of the corner position.

(3-Sec. 30) Found a 5/8" dia. rebar with red plastic cap stamped "R.Spear PS 43069" at the corner position, on the Range line between Section corner 1322.67' north and Quarter corner 1322.67' south. Accepted same as a careful and faithful establishment of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(10) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:  
 7" Balsam S86E 13.0' mrkd "1/16S BT"  
 7" Poplar S03W 16.0' do  
 6" Spruce S32W 26.9' do  
 12" Poplar N13W 39.6' do  
 Set cedar post adjacent. Bearings magnetic.

(3) Fd. 5/8" rebar with plastic cap #43069 Set measuring nail with MDNR tag in the side of:  
 5" W.Birch N84E 6.5' mrkd "1/16S BT"  
 12" W.Pine S27E 33.0' do  
 8" twin Maple S06W 21.0' do  
 10" W.Pine N05W 35.8' do  
 Set cedar post adjacent. Bearings magnetic.

Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 05/03/2010



For the Michigan Department of Natural Resources and Environment, Forest Management Division

16408  
16409