

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Iron	Located In:	Corner Code #
(County)		
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S 12 T 43N R 31W	15
	S 11 T 43N R 31W	13
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 15 04/30/2009 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(15-Sec. 12) West 1/16 corner between Sections 12 and 13. 1986 - K.L.Sackett RLS established the corner midway and on line between Section corner west and Quarter corner east. Set 1"IDx32" I.pipe with 4" alum. cap. 4" Balsam S40W 15.0', 8" Balsam N63E 48.6', 12" Sugar N06E 56.6'.

(13-Sec. 11) Southeast 1/16 corner, Sec. 11. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(15-Sec. 12) The 1986 monument was not recovered. The three 1986 NBTs were found: The Sugar NE in good condition with overgrown measuring notch, neither Balsam BT is alive - one a leaning stub, the other a lightning strike. These trees were not sufficient to accurately reestablish the 1986 position. The 1986 position was remonumented midway and on the Section line between Section corner 1320.70' west and Quarter corner 1320.70' east.

(13-Sec. 11) Established the corner at the intersection of straight lines connecting opposite 1/16 corners.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(15) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 17" Maple N08E 57.9' old blazes overgrown
 3" Y.Birch N68E 53.4' mrkd "1/16S BT"
 12" Maple S68W 45.0' do
 5" Poplar N35W 44.5' do
 Set sq'd Cedar post adjacent.
 Bearings are magnetic.

(13) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 3" Sugar S61W 40.5' mrkd "1/16S BT"
 13" Sugar N77W 28.2' do
 9" Sugar N01E 14.6' do
 4" Sugar S83E 41.3' do
 Set sq'd Cedar post adjacent.
 Bearings are magnetic.

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 06/09/2009



For the Michigan Department of Natural Resources, Office of Land and Facilities