

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Iron	Located In:	Corner Code #
(County)		
1. Public Land Survey	T 43N R 31W	K4
	T 43N R 31W	I4
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Stephan J. Szyszkoski, in a field survey on K4 04/30/2009 and I4 04/30/2009 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(K4) Quarter corner common to Sections 11 and 12. 1986 - Reestablished by K.L.Sackett RLS midway and on line between Section corners north and south. Set 1"IDx32" I.pipe with 4" alum. cap. 5" Sugar S34E 4.3', 8" Sugar S67W 13.0', 4" Sugar N30E 18.7', 4" sq'd Sugar S22W 3.5'.

(I4) Quarter corner common to Sections 10 and 11. 1965 - Remonumented by F.J.Bray RLS who replaced the corner from two old and one new wood posts which check for bearing and distance with two rotted cedar stumps which were original BTs. Signature tree in vicinity dates back to 1919. Set 1" Iron pipe with 4" aluminum cap. 9" Cedar N71W 21 links, 9" Cedar S45E 21 links, 6" Cedar S24W 23 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(K4) Found the 1986 monument and accessories in good condition but not at the record position. Specifically, the monument is located N88E 18.9' from the midway position intended in 1986. Since it appears that the monument in its current position has not been relied upon in the intervening years, I did not accept it as marking the position of the corner. I reestablished the corner at the position intended in 1986 - midway and on the Section line between Section corners 2641.46' north and south. The 1986 monument was removed.

(I4) Found the 1965 monument leaning heavily to the NE. Plumbed the monument and made it firm, at record bearing and distance from the SE and SW NBTs. The NW NBT is in place but it appears that the distance to it was incorrectly noted on the 1966 record.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(K4) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 12" Sugar N79W 0.95' mrkd "1/4S NBT"
 8" Sugar N52E 14.05' do
 7" Sugar S42E 26.7' do
 8" Sugar S21W 18.3' do
 Set sq'd Cedar post adjacent.
 Bearings are magnetic.

(I4) Found 1"ID I.pipe with 4" alum. MI Dept. of Conservation cap. Set measuring nail with MDNR tag in the side of:
 12" Cedar S37E 13.6' marks visible (1965 NBT)
 10" Cedar S29W 15.35' do do
 11" Cedar N67W 23.2' marks plain do
 7" Cedar N50E 23.6' mrkd "1/4S NBT"
 Cedar post adjacent. Bearings magnetic.

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 06/09/2009

For the Michigan Department of Natural Resources, Office of Land and Facilities

