

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Iron	Located In:	Corner Code #
(County)		
1. Public Land Survey	T 43N R 31W	H7
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S 16 T 43N R 31W	5
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 5 06/25/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(H7) Quarter corner common to Sections 15 and 22. 1849 - Established by John Burt, Deputy Surveyor, midway and on the Section line between Section corners 40.00 chains east and west. Set cedar post. Tamarack 8" N44E 21 links, Tamarack 10 S25W 33 links.

(5-Sec. 16) North 1/16 corner, Section 16. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(H7) The original post and accessories were not recovered. Found no acceptable evidence of the position of the original corner on the ground. Reestablished the corner midway and on the Section line between Section corners 2622.84' east and west. From the corner thus established, found an iron pipe, not of record, N02E 100.5' distant, which I did not accept as evidence of the position of the original corner.

(5-Sec. 16) Established the corner midway and on a straight line between Center of Section 1328.65' south and Quarter corner 1328.65' north.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(H7) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 6" Cedar N34W 14.75' mrkd "1/4S NBT"
 5" Cedar N83E 10.75' do
 5" Cedar S06W 15.6' do
 9" Cedar S46W 25.4' do
 Set cedar post adjacent. Bearings are magnetic.

(5) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 3" Cherry N34E 25.5' mrkd "1/16S BT"
 6" Cherry S15E 14.45' do
 11" Balsam S69W 15.3' do
 6" Poplar N04E 28.85' do
 Set cedar post adjacent. Bearings are magnetic.

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 07/14/2008

For the Michigan Department of Natural Resources, Office of Land and Facilities

