

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Iron	Located In:	Corner Code #
(County)		
1. Public Land Survey	T 43N R 31W	G6
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Stephan J. Szyszkoski, in a field survey on 06/23/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(G6) Quarter corner common to Sections 15 and 16. 1849 - Established by John Burt, Deputy Surveyor midway and on the Section line between Section corners 40.00 chains north and south. Set Elm post. Y.Birch 18 N66W 32 links, B.Ash 12 S35E 25 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(G6) The original post and accessories were not recovered. Found no acceptable evidence of the N-S position of the original corner on the ground. An improved public road runs along the north 1/2 mile of the line between Sections 15 and 16 and I accepted the location of the centerline as the best available evidence of the position of the easting of the original corner. Therefore, I reestablished the corner midway between Section corners 2655.75' north and south and on the centerline, extended southerly, of the paved county road. The position for the corner is 18.3' west of a straight line between Section corners.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(G6) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 7" Elm N70W 70.6' mrkd "1/4S NBT"
 5" Elm N49E 18.9' do
 7" Elm S79E 12.0' do
 power pole S54W 53.8' ID 40-5 97-01825
 Sq'd cedar post adjacent. Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 07/14/2008
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources, Office of Land and Facilities