

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Iron	Located In:	Corner Code #
(County)		
1. Public Land Survey	T _____ R _____	_____
	T <u>43N</u> R <u>31W</u>	<u>F7</u>
	T _____ R _____	_____
2. Property Controlling in Section	S <u>16</u> T <u>43N</u> R <u>31W</u>	<u>F6</u>
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		●		15		14		13		
7					●								
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on F7 06/24/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(F6) Center of Section 16. Not established in the original survey.

(F7) Quarter corner common to Sections 16 and 21. 1849 - Established by John Burt, Deputy Surveyor, midway and on the Section line between Section corners 40.00 chains east and west. Set Cedar post. Y. Birch 24" N21W 9 links, Fir 8" S53E 8 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(F6) Established the corner at the intersection of straight lines connecting opposite 1/4 corners. From the position thus established, which falls in a cleared pasture, an E-W fence is 52' south and a N-S fence is 19' west.

(F7) The original post and accessories were not recovered. Found no acceptable evidence of the position of the original corner on the ground. Reestablished the corner midway and on the Section line between Section corners 2622.85' east and west. From the position thus established, found a 3/4" ID I.pipe, placed by persons unknown, N15E 90.9' distant, which I did not accept as evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(F6) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 13" Sugar S16E 65.7' mrkd "C1/4 BT"
 19" Sugar S25W 51.3' do
 8" Poplar N88W 25.6' do
 9" Spruce N17W 54.6' do
 Sq'd cedar post adjacent. Bearings are magnetic.

(F7) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 7" Cedar N59E 54.6' mrkd "1/4S NBT"
 5" Spruce S18E 4.6' do
 20" Cedar S58W 57.0' do
 Util. pole N32W 31.55' ID N713131
 W. edge asphalt pavement is 10' east.
 Bearings are magnetic. Set post adjacent.

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 07/14/2008



For the Michigan Department of Natural Resources, Office of Land and Facilities