

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Iron (County)	Located In:	Corner Code #
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S 16 T 43N R 31W	10
	S 16 T 43N R 31W	15
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on 07/02/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(10-Sec. 16) South 1/16 corner between Sections 16 and 17. 1974 - Established midway and on line between Section and Quarter corners by A.O.Enger RLS. Set 1"IDx34" I.pipe with 3.5" alum. State of Michigan cap. Red Maple 9 N5E 43.4', Red Maple 9 S4W 16.6'.

(15-Sec. 16) West 1/16 corner between Sections 16 and 21. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(10-Sec. 16) Found the 1974 monument in good condition and at substantial record position, N26E 0.35' from the midway position between Section and Quarter corners. Accepted the monument as a careful and faithful establishment of the position of the corner. The 1974 Maple BT SW was found in good condition, blazes overgrown, at record bearing and distance.

(15-Sec. 16) Established the corner midway and on the Section line between Section corner 1311.42' west and Quarter corner 1311.42' east.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(10) Fd. 1"ID I.pipe with 3.5" alum. cap.
 Set measuring nail with MDNR tag in the side of:
 6" Spruce N78W 21.6' mrkd "1/16 BT"
 7" Spruce N37W 21.95' do
 5" Spruce S58E 9.15' do
 20" Maple S09W 16.2' old blazes (1974 NBT)
 Sq'd post adjacent. Bearings are magnetic.

(15) Set 1"IDx32" I.pipe with 4" alum. MDNR cap.
 Set measuring nail with MDNR tag in the side of:
 5" Balsam N20E 36.7' mrkd "1/16S BT"
 10" W.Birch S55E 23.3' do
 10" Y.Birch S05E 19.6' do
 16" Maple N86W 27.95' do
 Set sq'd post adjacent. Bearings are magnetic.

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 07/14/2008



For the Michigan Department of Natural Resources, Office of Land and Facilities

16091

16092