

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

Iron	Located In:	Corner Code #
(County)		
1. Public Land Survey	T 43N R 31W	F5
	T 43N R 31W	G7
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5					●								
6	18		17		16		15		14		13		
7							●						
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on F5 04/14/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

(F5) Quarter corner common to Sections 9-16. Corner of record approved by Iron County Peer Group Dec. 20, 2002 and recorded in Liber 10 of LCR, Page 11, Iron County Records. 1" Iron pipe with 3.5" aluminum State of Michigan cap. Spruce 7" N08W 21.71', Spruce 8" S58E 45.86', Spruce 7" S75W 33.87', Steel sign post S30W 0.60', Tamarack 14" N56W 75.58'

(G7) Corner common to Sections 15-16-21-22. 1849 - Established by John Burt, Deputy Surveyor. Set cedar post. Spruce 12 N35W 29 links, Tamarack 10 S58E 10 links.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(F5) Recovered the monument of record, at record bearing and distance from the 2002 witnesses. The Spruce SW is dead and down, and the Tamarack NW is a dead stub. Left the monument in place and made new witnesses, as described below.

(G7) The original post and accessories were not recovered. Found no acceptable evidence of the position of the original corner on the ground. Reestablished the corner by double proportionate measurement to the original record between Section corners 5311.38' north, 5311.03' south, 5245.68' east, and 5245.70' west.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(F5) Found 1" ID I.pipe with 3.5" alum. State of Michigan cap. Set measuring nail with MDNR tag in the side of:  
 6" Spruce S07E 26.2' mrkd "1/4S NBT"  
 6" Balsam N41W 10.3' do  
 Found nail/tag in:  
 8" Spruce S55E 45.9' with remon. poster  
 7" Spruce N01W 21.7' do  
 Sq'd post adjacent. Metal sign post 0.6' SW.

(G7) Set 1" IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:  
 6" Tamarack N24E 20.4' mrkd "S15 NBT"  
 5" Tamarack S70E 23.4' "S22 NBT"  
 6" B.Spruce S03W 17.35' "S21 NBT"  
 4" Tamarack N78W 9.9' "S16 NBT"  
 Set sq'd cedar post adjacent. Bearings magnetic.

Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 07/14/2008



For the Michigan Department of Natural Resources, Office of Land and Facilities