

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Iron</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 43N R 31W	E6
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S 16 T 43N R 31W	11
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on E6 07/01/2008 do hereby state
11 07/02/2008
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2
above were in conformance with regulations and rules therefore as required in the current manual of survey
instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of
a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,
re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded
on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

(E6) Quarter corner common to Sections 16-17. 1974 - Corner position reestablished by A.O.Enger RLS,
midway and on the Section line between Section corners 40.309 chains north and south. 1"IDx36"
I.pipe with 3.5" dia. alum. State of Michigan cap. Sugar Maple 5 N17W 22.9', Sugar Maple 6 S35E
25.9', Cedar 6 N04E 26.0'.

(11-Sec. 16) Southwest 1/16 corner, Sec. 16. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(E6) Recovered the 1974 monument in good condition, and substantially at the record position, N80W
0.8' from the midpoint between Section corners. The 1974 witness trees were not recovered. Accepted
the monument as a careful and faithful reestablishment of the position of the original corner.

(11-Sec. 16) Established the corner at the intersection of straight lines connecting opposite 1/16
corners.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(E6) Fd. 1"ID I.pipe with 3.5" alum. cap.
Set measuring nail with MDNR tag in the side of:
5" Sugar N39E 13.2' mrkd "1/4S NBT"
6" Balsam S87E 37.5' do
6" Sugar S20E 8.3' do
7" Y.Birch N40W 16.7' do
Set sq'd post adjacent. Bearings are magnetic.

(11) Set 1"IDx32" I.pipe with 4" alum. MDNR cap.
Set measuring nail with MDNR tag in the side of:
8" twin Maple N20W 43.25' mrkd "1/16S BT"
12" Maple N82E 21.5' do
4" Balsam S37E 21.3' do
12" triple Maple S37W 25.1' do
Set sq'd post adjacent. Bearings are magnetic.

Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 07/14/2008

For the Michigan Department of Natural Resources, Office of Land and Facilities

