

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>43</u> ^{N.} XX , R. <u>31</u> ^{XX} W.	D3 & E3
2. PROPERTY CONTROLLING IN SECTION _____	, T. _____, S., R. _____, E. _____, W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____, S., R. _____, E. _____, W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on September 26, 1975, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:
- Corner D3 (1/4 corner between Sections 5 & 8, T43N, R31W):
 - Cedar post (Not found. No subsequent monuments found.)
 - Cedar 10 N1W 7 (" " " " accessories ")
 - Cedar 10 S15W 5 (" " " " " ")
 - Corner E3 (Section Corner 4, 5, 8, & 9, T43N, R31W):
 - Y. Birch post (Not found. Found WMPC concrete monument
 - Cedar 10 N58W 25 (" " " " No subsequent accessories found.)
 - Hemlock 10 S15E 31 (" " " " " ")

- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- Corner D3: Placed witness monument on south shore of pond on N side of RR embankment, S0°11'W 68.76 ft. from calculated proportionate corner on line between Sec. Cor. 39.840 ch. E and 39.850 ch. W. True corner is in flooded area and no search could be made for it nor for a stream 1.35 ch. W of it, the course of which has been artificially re-routed.
 - Corner E3: According to WMPC maps, monument was set by reference to ties noted on old RR maps, but nothing else is known about it. It appears to be consistent with other corners in the area.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- Corner D3: 1" I.D. x 36" iron pipe with 33/4" aluminum cap for witness corner.
 - Balm-of-Gilead 5 S81°W (mag.) 18.1 ft. "1/4S, NBT"
 - Cherry 4 S50°E (mag.) 19.0 ft. "1/4S, NBT"

Note: NBT's are for the witness corner, not the true corner.

- Corner E3: Concrete monument with WMPC brass marker
 - Red Pine 6 N30°E (mag.) 36.9 ft. "S5, NBT"
 - Red Pine 4 N72°E (mag.) 30.4 ft. "S4, NBT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)
FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE March 30, 1976
MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger
Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

