

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER	
1. PUBLIC LAND SURVEY_____	T. <u>43</u> N. XX R. <u>31</u> XX W.	C6	REGISTER OF DEEDS STAMP AND FILING NUMBER
2. PROPERTY CONTROLL- ING IN SECTION <u>17</u>	T. <u>43</u> N. XX R. <u>31</u> XX W.	10	
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ R. _____ E. _____ W. _____		
4. LOT NO. _____, RECORDED PLAT _____			
5. PRIVATE CLAIMS _____			

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on see below 19___, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19___, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- Corner C6:** Cedar 7 for corner. See B, below, for subsequent monuments. No original witnesses.
- Corner 10:** Not established in original survey. Presumably established c.1893, according to an existing map of the unrecorded Ferry & Calhoun Plat of the Village of Mansfield. Found an old 6" spike placed vertically in ground, and not attributable to casual construction activity, which appears to conform to the plat.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- Corner C6:** This corner re-witnessed on 9/19/60 and recorded on 3/17/61 by B. D. Buckle R.L.S. 8887, who placed the monument and witnesses shown in C below, and stated as follows: "This corner was replaced at Iron Pipe set by unknown surveyor. Have report of a wood stake in this position in 1941, found by Wisconsin-Michigan Power Company Surveyors. Position checks well with other corners in area."
- Corner 10:** Accepted the 6" spike as probably being the NE corner of old F. & C. plat, even though not on line or equidistant between corners to N and S of it. On 4/26/74 re-placed spike with new monument shown at C, below, which bears S0°36.5'E 1310.2 ft. from Corner C6 and N0°49.5'W 1334.3 ft. from Cor. C7.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Corner C6:** 1" I.D. x 48" iron pipe with 4" brass cap.
Elm 10 S6°E (mag.) 38 links "1/4S, NBT"
Sugar Maple 7 N25°W (mag.) 36 links "1/4S, NBT"
- Corner 10:** 1" I.D. x 36" iron pipe with 3½" aluminum cap.
Sugar Maple 11 N11½°E (mag.) 35.6 ft. "1/16S, BT"
Tamarack 6 S29°W (mag.) 49.4 ft. "1/16S, BT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ CHIEF OF SURVEY PARTY DATE _____

APPROVED AND SIGNED BY Arthur O. Enger MICHIGAN REGISTERED LAND SURVEYOR DATE September 17, 1974

Arthur O. Enger
Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

