

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>43</u> N. <del>XX</del> R. <u>31</u> <del>XX</del> W.	<u>C7</u>
2. PROPERTY CONTROLLING IN SECTION <u>17</u>	T. <u>43</u> N. <del>XX</del> R. <u>31</u> <del>XX</del> W.	<u>12</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ S. R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970 the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on see below 19\_\_\_\_, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

**Corner C7:** Sugar post (Not found. No subsequent monuments found.)  
 Y. Birch 24 S65W 19 ( " " " " accessories " )  
 Y. Birch 26 N46E 26 ( " " " " " " )

**Corner 12:** Not established in original survey nor subsequently, apparently.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

**Corner C7:** Re-established 4/26/74 by proportionate measurement in latitude and 2647.0 ft. E'ly of a monument at the 1/4 cor. bet. Sec. 18 & 19, which has color of being at the original corner position, for departure. The 2647.0 ft. distance was used as the unrecorded Ferry & Calhoun Plat of Village of Mansfield, which encompasses the SE 1/4 SE 1/4, Sec. 18, indicates its South boundary as being half that distance in length. The corner position thus chosen agrees with field note calls to a swamp edge 4 ch. S and the top of a granite knob 5 ch. N, and is on line with the centerline of an old E-W road beginning about 6 ch. W of corner. Position also agrees very closely with observed old lot and street lines of the now abandoned Village of Mansfield.

**Corner 12:** Established 5/9/74 on true N & S 1/4 line, 1326.4 ft. N of S 1/4 cor. and 1326.4 ft. S of Center 1/4 cor.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

**Monuments for both corners:** 1" I.D. x 36" iron pipe with 3 1/2" aluminum cap.

**Witnesses for Corner C7:** ⊕ chiselled in rock outcrop S21°51'35"E 88.87 ft.  
 ⊕ chiselled in rock outcrop S58°09'25"W 46.56 ft.

**Witnesses for Corner 12:** Red Maple 8 N20°W (mag.) 40.4 ft. "1/16S, BT"  
 Red Maple 4 N84°E (mag.) 38.9 ft. "1/16S, BT"

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Arthur O. Enger CHIEF OF SURVEY PARTY DATE September 17, 1974  
MICHIGAN REGISTERED LAND SURVEYOR

**Arthur O. Enger**  
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

