

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. 43 N. 2, R. 31 E. W.	E6
2. PROPERTY CONTROLLING IN SECTION 17_____	T. 43 N. 2, R. 31 E. W.	9 & 14
3. MISCELLANEOUS PROPERTY IN SECTION_____	T. _____ N. S., R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on see below 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner E6: Wood post (Not found. No subsequent monuments found.)
 Sugar 12 N20E 55 (" " " " accessories ")
 Fir 12 N29W 67 (" " " " " ")

Corners 9 & 14: Not established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner E6: Re-established 4/25/74 on line between Sec. Corners 40.309 ch. to N and to S.
 Corner 9: Established 5/10/74 on true E & W ½ line 19.989 ch. W of E½ cor. and 19.989 ch. E of Center ½ cor.
 Corner 14: Established 5/13/74 on line between ½ cor. 20.154 ch. N and Sec. Cor. 20.155 ch. S.

Note: See L. 1 of Survey Maps, P.10-21 for additional information.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Monuments for Corners E6 & 9: 1" I.D. x 36" iron pipe with 3½" aluminum cap.
 Witnesses for Corner E6: Sugar Maple 5 N17°W (mag.) 22.9 ft. "1/4S, NBT"
 Sugar Maple 6 S35°E (mag.) 25.9 ft. "1/4S, NBT"
 Cedar 6 N 4° E (mag.) 26.0 ft. "1/4S, NBT"
 Witnesses for Corner 9: Sugar Maple 8 N56°W (mag.) 33.5 ft. "1/16S, BT"
 Red Maple 12 S 3°W (mag.) 28.8 ft. "1/16S, BT"
 Corner 14: 1" I.D. x 34" iron pipe with 3½" aluminum cap.
 Red Maple 9 N5°E (mag.) 43.4 ft. "1/16S, BT"
 Red Maple 9 S4°W (mag.) 16.6 ft. "1/16S, BT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE _____
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

