

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. <u>43</u> N. S., R. <u>31</u> W.	E5
2. PROPERTY CONTROLLING IN SECTION	<u>17</u> , T. <u>43</u> N. S., R. <u>31</u> W.	2 & 7
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ N. S., R. _____ W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on see below 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner E5: Cedar post (Not found. No subsequent monuments found.)
 Hemlock 18 N32W 34 (" " " " accessories ")
 Hemlock 22 N34E 20 (" " " " " ")

Corner 2 & 7: Not established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner E5: Re-established 4/25/74 by proportionate measurements from corners 1 mile W and 1 mile E and at record distance S of a stream crossing to N. See Liber 1 of Survey Maps, P.10-20 for additional information as to re-establishment.
Corner 2: Established 5/10/74 on line between 1/4 cor. 19.965 ch. W and Sec. Cor. 19.965 ch. E.
Corner 7: Established 5/13/74 on line between Sec. Cor. 20.154 ch. N and 1/4 cor. 20.154 ch. S.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner E5: 1" I.D. x 40" iron pipe with 3½" aluminum cap.
 Sugar Maple 9 S71°W (mag.) 43.4 ft. "S17, NBT"
 Sugar Maple 6 N 1°W (mag.) 22.7 ft. "S 8, NBT"
 Sugar Maple 5 S19°E (mag.) 29.6 ft. "S16, NBT"
Corner 2: 1" I.D. x 36" iron pipe with 3½" aluminum cap.
 Sugar Maple 10 S47°W (mag.) 17.6 ft. "1/16S, BT"
 Cedar 12 N52°W (mag.) 27.0 ft. "1/16S, BT"
Corner 7: 1" I.D. x 36" iron pipe with 3½" aluminum cap.
 Balm-of-Gilead 5 N16°W (mag.) 11.5 ft. "1/16S, BT"
 Balm-of-Gilead 7 N55°E (mag.) 19.0 ft. "1/16S, BT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE March 31, 1974
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

