

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. <u>43</u> N. <u>31</u> E. <u>W.</u>	<u>E4</u>
2. PROPERTY CONTROLLING IN SECTION <u>8</u>	T. <u>43</u> N. <u>31</u> E. <u>W.</u>	<u>7 & 14</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ E. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on May 16, 1974 ~~XXXXX~~ established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner E4: Wood post (Not found. No subsequent monuments found.)
 Y. Birch 14 N35W 20 (Not found. No subsequent accessories found.)
 Fir 14 S39E 12 (Not found. No subsequent accessories found.)

Corners 7 & 14: Not established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner E4: Re-established on line between Sec. Cor. 40.545 ch. to N and to S.
Corner 7: Established on line between 1/4 cor. 20.273 ch. S and Sec. Cor. 20.272 ch. N.
Corner 14: Established on line between 1/4 cor. 20.273 ch. N and Sec. Cor. 20.272 ch. S.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner E4: 1" I.D. x 38" iron pipe with 3 1/2" aluminum cap.
 W. Pine 5 S25°W (mag.) 57.2 ft. "1/4S, NBT"
 W. Pine 6 S36 1/2°E (mag.) 97.2 ft. "1/4S, NBT"

Corner 7: 1" I.D. x 36" iron pipe with 3 1/2" aluminum cap.
 Tamarack 5 N75°E (mag.) 50.7 ft. "1/16S, BT"
 W. Pine 5 N49°W (mag.) 16.2 ft. "1/16S, BT"

Corner 14: 1" I.D. x 36" iron pipe with 3 1/2" aluminum cap.
 W. Spruce 13 S37°E (mag.) 37.9 ft. "1/16S, BT"
 B. Spruce 9 N63°W (mag.) 20.9 ft. "1/16S, BT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE March 31, 1978
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

