

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>43</u> N. <u>W.</u> , R. <u>31</u> W.	F5
2. PROPERTY CONTROLLING IN SECTION <u>16</u>	T. <u>43</u> N. <u>W.</u> , R. <u>31</u> W.	1 & 2
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____, R. _____ E. _____ W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on May 15 19 74, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner F5: Cedar post (Not found. No subsequent monuments found.)
 Cedar 18 N11E 84 (" " " " accessories ")
 Spruce 10 S66W 21 (" " " " " ")

Corners 1 & 2: Not established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner F5: Re-established on line between Sec. Cor. 39.799 ch. to E and to W. See L. 1 of Survey Maps, P. 10-20 for additional information.

Corner 1: Established on line between Sec. Cor. 19.900 ch. W and 1/4 cor. 19.900 ch. E.

Corner 2: Established on line between Sec. Cor. 19.900 ch. E and 1/4 cor. 19.900 ch. W.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Monuments for all three corners: 1" I.D. x 36" iron pipe with 3 1/4" aluminum cap.

Witnesses for Corner F5: Tamarack 10 N57°W (mag.) 75.3 ft. "1/4S, NBT"

W. Spruce 11 S68°W (mag.) 26.7 ft. "1/4S, NBT"

Witnesses for Corner 1: Red Maple 5 N65°W (mag.) 9.1 ft. "1/16S, BT"

Cedar 18 S25°W (mag.) 35.3 ft. "1/16S, BT"

Witnesses for Corner 2: Cedar 7 S82°W (mag.) 20.5 ft. "1/16S, BT"

Cedar 7 N 5°E (mag.) 22.1 ft. "1/16S, BT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ CHIEF OF SURVEY PARTY DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE March 31, 1975

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

