

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 43 N.R. 31 W


Iron COUNTY

DESCRIPTION OF CORNER Witness corner for Sections 17 and 20 on West side of Michigamme River.

CORNER MONUMENT 1" x 48" Iron Pipe

DATE MONUMENT PLACED AND WITNESSED 9/16/60

WITNESSES TO CORNER..... 10" Cedar (BT) N 43° E 180 1/2 Links



10" Cedar (BT) N 81° E 62 Links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was placed on line between Section Corner to West and 1/4 Corner to East and on bank of lagoon which was original river bed. Corner lies 13.335 chains East of Section Corner 17, 18, 19, 20.

SURVEYOR'S SEAL

SIGNED

Billy D. Buckler

REGISTERED LAND SURVEYOR

Billy D. Buckler

DATE

3/17/61