


STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

Iron COUNTY
T 43N R 31W

DESCRIPTION OF CORNER Section Corner 21, 22, 27 and 28
CORNER MONUMENT 1" I. D. x 36" iron pipe with 4" aluminum cap
DATE MONUMENT PLACED AND WITNESSED October 21, 1968
WITNESSES TO CORNER..... Cedar 9 N73°W 19 lks. "S21 NBT"



Cedar 5 S68°W 23 lks. "S28 NBT"
Cedar 15 S17°E 44 lks. "S27 NBT"
AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Monument placed at site of two squared cedar posts, both of which bear N18°W 9 lks. from a badly rotted cedar stump corresponding to an original BT, Cedar 12 S18E 9. No marks on stump or on down bole of same lying nearby.

Found a "Section Tree" believed to be a mark of the original government survey, bearing S67°W 44½ lks. from the corner position. This is a dead 16" cedar stub with only an upper description blaze bearing scribe marks "S28" very plain. No witness blaze. These infrequently found marked trees were not recorded in the original field notes, and were evidently made only as additional marking of the corner site. The undersigned has seen several of these in Marquette County, but this is the first seen in Iron County. No evidence of a hemlock BT.

Also found point of a 1" cedar post in the muck at the corner, which may be part of the original corner post. Also found several old blazes and cruiser register trees about the corner, with the oldest legible name being "Walter 10/15/41." Informed about corner by Tony Sailer, Kimberly-Clark Corp. Forestry Aide.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Arthur P. Enger
REGISTERED LAND SURVEYOR

DATE

3/19/69

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68