


STATE OF MICHIGAN  
DEPARTMENT  
OF  
NATURAL RESOURCES

LAND CORNER RECORD

Iron COUNTY  
T 43N R 31-32W

DESCRIPTION OF CORNER 1/4 corner between Sections 25 and 30  
CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap  
DATE MONUMENT PLACED AND WITNESSED May 2, 1972  
WITNESSES TO CORNER..... Cedar 6 (E. one of twins) S 7°E (mag.) 3.9 ft. "1/4S, NBT"



Cedar 6 N58°E (mag.) 28.3 ft. "1/4S, NBT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Corner re-established by proportionate measurement on line between section corners 40.102 ch. to N and to S. Position agrees with original field note calls to a rock ledge 2.00 ch. N and a stream crossing 13.25 ch. S.

Variation 5°05' East at this corner.

SURVEYOR'S SEAL

DISTRIBUTION:

Forestry Division, Lansing

Area Forester

District Surveyor

SIGNED

*Arthur O. Enger*  
REGISTERED LAND SURVEYOR  
Arthur O. Enger

DATE June 26, 1972