

LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

Iron County

FOR CORNERS OF--

LOCATED IN--

CORNER CODE NUMBER

1. PUBLIC LAND SURVEY	T. 43	N. R. 31	E. W.	B9, C10, C9, B11
2. PROPERTY CONTROLLING IN SECTION	T. _____	N. S. R. _____	E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____	N. S. R. _____	E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____				
5. PRIVATE CLAIMS _____				

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on May 20, 1985, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner B9: Original monument and accessories not found.
 Corner C10: Original monument and accessories not found.
 Corner C9: Original monument and accessories not found.
 Corner B11: Original monument and accessories not found.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner B9: Restored by proportion on line between corners east and west.
 Corner C10: Restored midway and on line between corners north and south.
 Corner C9: Restored by double proportion distance.
 Corner B11: Restored on line by proportion between corners east and west.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner B9: Set 1" I.D. by 32" I.P. with 4" alum. cap	Corner C9: Set 1" I.D. by 32" I.P.
5" cedar N10E 28.1' ¼S, NBT	w/4"/ac 12" Cedar N76W 7.6' S19,NBT
7" cedar N76W 39.9' ¼S, NBT	12" Cedar S01E 9.0' S29,NBT
6" balsam S60E 34.5' ¼S, NBT	Power pole N44E 44.3'
Corner C10: Set 1" I.D. by 32" I.P.	Corner B11: Set 1" I.D. by 32" I.P. w/4"/a.c.
8" cedar S35W 54.5' ¼S, NBT	22" W.Pine N32W 7.1' ¼S, NBT
10" tamarack N80W 7.3' ¼S, NBT	6" cedar N25E 30.0' ¼S, NBT
Power pole N19E 71.1'	4" spruce S05E 6.0' ¼S, NBT

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (REAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Keith L. Sackett DATE _____

CHIEF OF SURVEY PARTY
 MICHIGAN REGISTERED LAND SURVEYOR
 Keith L. Sackett
 Department of Natural Resources

(REAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006