

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Iron

(County)	Located in:	Corner Code #?
1. Public Land Survey	T 42N R 31W	A11
	T R	A12
	T R	
	T R	
2. Property Controlling in Section	S 31	10
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4 Lot No. _____, Recorded Plat _____
5 Private Claims _____

I, **Keith Backett**, in a field survey on See below, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	18	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:


A11	A12	10
Original monument and accessories not found. Found Wisconsin-Michigan Power Co. monument.	Original monument and accessories not found.	Not set on original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A11	A12	10
10-6-87 Restored at MI-MI Power Co. monument.	10-11-87 Restored midway on line.	11-10-87 Established midway on line.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A11	A12	10
MI-MI Power Co. monument. 4" white pine N10E 8.6' 830 NBT	Set 1" I.D. x 32" I.P. w/4" aluminum cap. 5" spruce 849E 8.4' 1/4S NBT 4" spruce 864W 5.6' 1/4S NBT 5" spruce N32W 11.4' 1/4S NBT	Set 1" I.D. x 32" I.P. w/4" aluminum cap. 24" white pine 889E 8.5' 1/16S BT 5" maple 831W 12.0' 1/16S BT 8" maple N34W 23.4' 1/16S BT



Signed by *Keith Backett*

Date 2-26-88

Surveyor's Michigan License No. 19066