

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Iron (County)	Located In:	Corner Code #
1. Public Land Survey	T 43N R 31W	CS
	T 43N R 31W	AS
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3		●											
4	7	8	9	10	11	12							
5	●												
6	15	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Stephan J. Szyzkowski, in a field survey on February 21, 1993, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(CS) Section corner common to sections 5-6-7-8. Corner previously recorded by Arthur D. Enger in 1976 as monumented by a Concrete monument with MNPC brass marker and the following NBTs: Tamarack 15 N49W (mag.) 90.9' "S6, NBT", Tamarack 20 N56E (mag.) 87.7' "S5, NBT", MNPC Power pole 3N61-2160 W14 1/2N (mag.) 52.06' to tack with 3/4" brass washer stamped "WITNESS MARK". Found no subsequent record.

(AS) Section corner common to Sections 7-10, T43N-R31W, and Sections 12-13, T43N-R32W. Corner previously recorded by Dean C. DeLaHater in 1953 as monumented by a 1" pipe with a 4" brass cap and witnessed by the following NBTs: 6" Cedar East 64 links, 6" Cedar N25E 14 links. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(CS) Found Enger's tamarack NBTs and the stub of a sawed-off power pole all in proper relation to each other. The monument itself was not recovered. Old blazes on the tamaracks are visible and they are both still alive. The power pole appears to have been cut off below the level of the tack and washer, as these were not found. Placed a new monument, a 1"x32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet at record bearing and distance from the witnesses described above, and marked two new bearing trees as described below.

(AS) Found a 1" pipe with a 4" brass Michigan Dept. of Conservation cap substantially in accord with the record NBTs as follows: Cedar NBT N25E 9.2' found at record bearing and distance with old blaze but no scribing, Cedar NBT found S80E, 42.4' (rather than East) with old blaze, no scribing. Marked two new witnesses to the monument as described below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(CS) Set 1" pipe with a 4" MDNR cap.	(AS) Found 1" pipe with 4" brass cap.
Marked the following new bearing trees:	New witnesses are as follows:
6" Spruce N85E 100.0' "S5 NBT"	7" Cedar N80W 14.0' "S12 NBT"
8" Balsam N30W 81.9' "S6 NBT"	Power pole S11W 41.37' Set nail and brass tag stamped "MDNR reference point".

Signed by Stephan J. Szyzkowski Date 3-23-93
Surveyor's Michigan License No. 33986