

**SURVEY &  
REMONUMENTATION**

**JAN 19 1999**

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Iron (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>43N</u> R <u>32W</u>	<u>B-11</u>
	T ___ R ___	___
	T ___ R ___	___
	T ___ R ___	___
2. Property Controlling in Section	S ___ T ___ R ___	___
	S ___ T ___ R ___	___
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	___
	S ___ T ___ R ___	___

**IRON COUNTY  
MICHIGAN  
RECEIVED FOR RECORD**  
98 DEC 28 AM 11:12  
L.C. Records: L. 7, P. 242  
*Gail... [Signature]*  
REGISTERED LAND SURVEYORS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

Quarter Corner Sections 30 and 31, T43N, R32W

I, Gary L. Pisoni, in a field survey on October 24, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5			4			3		2	1
3													
4	7			8			9			10		11	12
5													
6	18			17			16			15		14	13
7													
8	19			20			21			22		23	24
9													
10	30			29			28			27		26	25
11													
12	31			32			33			34		35	36
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established on August 9, 1849 by Zelotes B. Searls, U.S. Deputy Surveyor.

Original Corner; Sugar Post

Original Bearing Trees:

Yellow Birch	18"	S 81°W	32 lks (21.12 feet)
Sugar	6"	East	07 lks (4.62 feet)

On 11-27-68, Arthur O. Enger, RLS with the Michigan Dept. Of Natural Resources found a 1 1/4" O.D. iron pipe in place at the intersection of the Northerly extension of an old N & S fence line South of the corner and the Westerly extension of an E & W section of county road to the East of corner. Replaced the iron pipe with a 1" dia. x 36" iron pipe with 4" dia. aluminum cap, stamped as follows: DNR, T43N, R32W, 1/4, S-30, S-31, 1968, RLS 13581, recorded in L.C. Certificate Liber 2, Page 526 on 1/22/69.

1968 Bearing Trees:

Elm	5"	S 87°E	35 lks (23.10 feet)
White Birch	5"	S 44°E	19 lks (12.54 feet)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of original B.T.s found.

Found monument as set by Arthur O. Enger in 1968 and the following bearing tree:

White Birch	14"	S 38° E	12.83 feet
-------------	-----	---------	------------

Corner record research on file with county representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Blazed and scribed the following new bearing trees: (All measurement taken to a nail in side of tree)

White Birch	12"	N 82° E	38.15 feet
Elm	12"	N 74° W	19.02 feet
Steel sign post		S 39° W	0.75 feet

98-8

Signed by Gary L. Pisoni

Date 12-21-98

Surveyor's Michigan License No. 27457

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN 28, 1971



L. 7 P. 242