

**SURVEY &  
REMONUMENTATION**

JAN 19 1999

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Iron</u> (County)	Located in:	Corner Code #
1. Public Land Survey	<u>T 43N R 32W</u>	<u>C-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

IRON COUNTY  
MICHIGAN  
RECEIVED FOR RECORD

98 DEC 28 AM 11:23  
*L.C. Records Lib. 73 P. 302*  
*Gilbert L. Pisoni*  
REGISTERED LAND SURVEYOR

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

Section Corner Sections 17, 18, 19 and 20, T43N, R32W

I, Gary L. Pisoni, in a field survey on Dec. 12, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7			●										
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

**A. Description of original monument and accessories and/or subsequent restoration:**

Original corner established on August 9, 1849 by Zelotes B. Searls, U.S. Deputy Surveyor.  
Original Corner; Maple Post  
Original Bearing Trees:

White Birch	16"	S 40°W	21 lks (13.86 feet)
Cedar	10"	N 24° E	29 lks (19.14 feet)

On 6/8/94, Stephan J. Szyszkoski, RLS with the Michigan Dept. of Natural Resources found a 1" diameter solid iron bar located in a rock outcrop, iron bar was probably set by the local mining company. He accepted the iron bar as the best available evidence of the position of the original corner, recorded in L.C. Certificate, Liber 6, Page 320 in 1994.

1994 Bearing Trees:

Maple	5"	N 44°E	20.9 feet
Spruce	10"	S 14°E	20.6 feet
Maple	7"	N 87° W	19.9 feet
Maple	5"	S 20 °W	13.6 feet

PEER GROUP APPROVED  
Iron A. Pisoni 12-18-98  
COUNTY REPRESENTATIVE

I accept the iron bar as the best available evidence for restoring the corner position.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

No evidence of original B.T.s found. Found iron bar as described above, 17" above ground surface and the following bearing trees:

Red Maple	4"	N 44°E	20.95 feet
Spruce	11"	S 13°E	20.64 feet
Red Maple	6"	S 19°W	13.72 feet
Red Maple	7"	West	20.05 feet

Corner record research on file with county representative.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the**

98-150  
Signed by Gary L. Pisoni Date 12-21-98  
Surveyor's Michigan License No. 27457



FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983  
REVISED OCT., 1995

L. 7 P. 302