

**SURVEY &
REMONUMENTATION**

JAN 19 1999

SECTION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Iron (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>43N</u> R <u>32W</u>	<u>C-10</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

**IRON COUNTY
MICHIGAN
RECEIVED FOR RECORD**

98 DEC 28 AM 11:11

L.C. Records: L. 7, P. 240

Gilbert J. Pisoni
REGISTERED LAND SURVEYOR

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Quarter Corner Sections 30 and 29, T43N, R32W

I, Gary L. Pisoni, in a field survey on October 22, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established in 1849 by Zelotes B. Searls, U.S. Deputy Surveyor
Original Corner; Maple Post
Original Bearing Trees:
Cedar 18" S 39°E 09 lks (5.94 feet)
Cedar 12" S 84°W 26 lks (17.16 feet)

On 11-27-68, Arthur O. Enger, RLS with the Michigan Dept. Of Natural Resources, found a plat monument which is shown on the Plat of Odgers (1942) as the Southeast corner of said plat and the SE 1/4 of NE 1/4, Section 30, recorded in L.C. Certificate, Liber 2, Page 523 on 1/20/69.

1968 Bearing Trees:
Power Pole N 32°W 81 lks (53.46 feet)
Telephone Pole #E2404 S 48°E 113 lks (74.58 feet)
Telephone Pole #E2405 S 47°W 73.5 lks (48.51 feet)
Plat Monument N 00°01' W 64.00 feet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of original B.T.s found.

Found monument as described above and the following reference object:
Plat monument (Iron bar in concrete) N 0° 01'W 64.00 feet
No other references found.

Monument located on the South edge of County Road and 8" below gravel surface.
Distances to the North and South Section corners are consistent with GLO distances.

Corner record research on file with county representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Set one (1) reference monument being a 5/8" diameter by 30" long rebar pin with a 3" diameter aluminum cap stamped as follows: Iron County Remonumentation, T43N, R32W, R.M., 1/4, S-29, S30, N 34° W, 19.11', 1998, RLS 27457 from which I established the following new blazed and scribed bearing trees: (All measurements taken to a nail in side of tree)

Yellow Birch	8" dbl	S 64° E	55.43 feet
Hemlock	11"	S 46° W	39.04 feet
R.M.	5/8"x30" rebar	S 34° E	19.11 feet
Steel sign post		S 34° E	19.61 feet

PEER GROUP APPROVED
Iron H. Pisoni 11-21-98
COUNTY REPRESENTATIVE

98-5
Signed by Gary L. Pisoni Date 11-21-98
Surveyor's Michigan License No. 27457

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983
REVISED OCT., 1995



L. 7 P. 240