

SURVEY & REMONUMENTATION

JAN 19 1999

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Iron</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>43N</u> R <u>32W</u>	<u>D-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

IRON COUNTY MICHIGAN
RECEIVED FOR RECORD

98 DEC 28 AM 11:23
L.C. Records: L. 7, P. 306
Gilbert Pisoni
REGISTERED LAND SURVEYOR

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Quarter Corner Sections 8 and 17, T43N, R32W

I, Gary L. Pisoni, in a field survey on Dec. 3, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established on August 17, 1849 by Zelotes B. Searls, U.S. Deputy Surveyor.
Original Corner: Cedar Wood Post

Original Bearing Trees:

White Pine	28"	S 86° W	23 lks (15.18 feet)
Cedar	18"	N 15° E	11 lks (7.26 feet)

On 6/8/94, Stephan J. Szyszkoski, RLS with the Michigan Dept. of Natural Resources found a 5/8" diameter iron pin 6" below the road bed surface of Rock Crusher Road. He accepted the iron pin as recovered as being a careful and faithful re-establishment of the corner position, recorded in L.C. Certificate, Liber 6, Page 319 in 1994.

1994 Bearing Trees:

Red Pine	11"	N 48°W	50.20 feet
Jack Pine	12"	N 86°E	23.99 feet
Red Pine	12"	S 13°E	34.26 feet
Red Pine	14"	N 82°W	42.59 feet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of original B.T.s found. Found iron pin as described above, 6" below road bed surface and located on the East edge of Rock Crusher Road and the following bearing trees:

Red Pine	11"	N 50°W	50.22 feet
Jack Pine	12"	N 83°E	24.00 feet
Red Pine	14"	S 14°E	34.24 feet
Red Pine	15"	N 84° 30' W	42.59 feet

PEER GROUP APPROVED
From J. Pisoni 12-18-98
COUNTY REPRESENTATIVE

Corner record research on file with County Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

From the above described corner position, I set a reference monument, being a 5/8" diameter by 30" long rebar, with a 3" aluminum cap stamped as follows:
Iron County Remonumentation, T43N, R32W, R.M., 1/4, S-8, S-17, N 75°W, 14.31', 1998, RLS 27457, from which the following reference object bears:

R.M.	5/8" x 30" rebar	S 75° E	14.31 feet
Steel sign post		S 75° E	14.75 feet

98-1
Signed by Gary L. Pisoni Date 12-21-98
Surveyor's Michigan License No. 27457

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983
REVISED OCT., 1995



L.7 P. 306