

SURVEY & REMONUMENTATION

JAN 19 1999

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Iron</u> (County)	Located In:	Corner Code #	
1. Public Land Survey	T <u>43N</u> R <u>32W</u>	<u>E-7</u>	
	T _____ R _____	_____	_____
	T _____ R _____	_____	_____
	T _____ R _____	_____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____	_____
	S _____ T _____ R _____	_____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	_____
	S _____ T _____ R _____	_____	_____

IRON COUNTY
MICHIGAN
RECEIVED FOR RECORD

98 DEC 28 AM 11:23
L.C. Records: L. 7, P. 305
Gary L. Pisoni
REGISTERED LAND SURVEYOR

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Section Corner Sections 17, 16, 20, 21, T43N, R32W

I, Gary L. Pisoni, in a field survey on Dec. 3, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4				7		8		9		10		11	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established on August 13, 1849 by Zelotes B. Searls, U.S. Deputy Surveyor.
Original Corner: Cedar Wood Post
Original Bearing Trees:

Tamarack	12"	S 41° W	30 lks (19.80 feet)
Tamarack	10"	N 74° E	47 lks (31.02 feet)

On 6/8/94, Stephan J. Szyszkoski, RLS with the Michigan Dept. of Natural Resources found a 5" diameter concrete filled stove pipe with a drill rod in center projecting 18" above ground surface in a tag alder swamp. Monument was probably set by the local mining company. He accepted the concrete monument as the best available evidence of the position of the original corner, recorded in L.C. Certificate, Liber 6, Page 320 in 1994.

1994 Bearing Trees:

Tamarack	12"	N 42° W	100.1 feet
Balsam	5"	S 66° E	34.7 feet
Balsam	5"	N 74° E	55.3 feet
Iron Pin	5/8" diameter stamped CF20	N 83° E	27.85 feet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of original B.T.s found. Found concrete monument as described above, 18" above ground surface and the following bearing trees:

Tamarack	16"	N 43° W	100.10 feet
Balsam	7"	S 67°30' E	34.69 feet
Balsam	7"	N 75° E	55.30 feet
Iron Pin	5/8" diameter stamped CF20	N 83° E	27.85 feet

Corner record research on file with County Representative.

PEER GROUP APPROVED
Gary L. Pisoni 12-21-98
COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

From the above described corner position, I set a reference monument, being a 3/4" dia. aluminum rod monument, 4' long, with a 3" aluminum cap stamped as follows:
Iron County Remonumentation, T43N, R32W, R.M., S-16, S-17, S-20, S-21, N 66° E, 1.34', 1998, RLS 27457, from which the following reference object bears:

R.M.	Aluminum rod mon.	S 66° W	1.34 feet
	Centerline of railroad grade	N 75° E	44.00 feet
	Steel sign post	S 66° W	1.90 feet

98-3
Signed by Gary L. Pisoni Date 12-21-98
Surveyor's Michigan License No. 27457

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983
REVISED OCT., 1995



L. 7 P. 305