

SURVEY & REMONUMENTATION

JAN 19 1999

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Iron</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>43N</u> R <u>32W</u>	<u>E-8</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

IRON COUNTY MICHIGAN
RECEIVED FOR RECORD

98 DEC 28 AM 11:23
L.C. Records: L. 7, P. 304
Eileen Stebie

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Quarter Corner Sections 20 and 21, T43N, R32W

I, Gary L. Pisoni, in a field survey on Dec. 3, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established August 13, 1849 by Zelotes B. Searls, U.S. Deputy Surveyor.

Original Corner: Hemlock Wood Post
Original Bearing Trees:

Sugar	18"	S 65° E	38 lks (25.08 feet)
Cedar	20"	N 78° W	33 lks (21.78 feet)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of original B.T.s found. Found a 1" diameter iron bar encased in concrete and flush with ground surface, located on the North side of a railroad grade, corner position was set by the local mining company.

I accept the concrete monument as the best available evidence for restoring the corner position.

Distance along the Section line is consistent with GLO distances.

Corner record research on file with county representative.

PEER GROUP APPROVED

Iron A. Pisoni 12-18-98
COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

From the above described corner position, I set a reference monument, being 5/8" diameter by 30" long rebar, with a 3" aluminum cap stamped as follows:
Iron County Remonumentation, T43N, R32W, R.M., 1/4, S-20, S-21, S 69° W, 1.20', 1998, RLS 27457, from which I blazed and scribed the following new bearing trees: (All measurements taken to a nail in side of tree)

White Birch	14"	N 03° E	12.64 feet
Popple	13"	S 42° E	22.40 feet
Popple	16"	S 09° W	13.65 feet
Popple	9"	N 69° W	22.90 feet
R.M.	5/8" x 30" rebar	N 69° E	1.20 feet
Steel sign post		N 69° E	1.95 feet

98-4

Signed by Gary L. Pisoni Date 12-21-98

Surveyor's Michigan License No. 27457

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983
REVISED OCT., 1995



L. 7 P. 304