

SECTION
 MAR 09 2000

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

| | | |
|------------------------------------|---------------------------|---------------|
| Iron | Located In: | Corner Code # |
| (County) | | |
| 1. Public Land Survey | T <u>43N</u> R <u>32W</u> | <u>E-11</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

IRON COUNTY
 MICHIGAN
 RECEIVED FOR RECORD

99 DEC 30 AM 10:25
 L.C. Records: L.8, P.92
Richard Stebbins
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Section Corner to Sections 28, 29, 32, 33, T43N, R32W

I, Gary L. Pisoni, in a field survey on April 22, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

| | | | | | | | | | | | | | |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 1 | | | | | | | | | | | | | |
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | | |
| 13 | | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established on August 10, 1849 by Z. B. Searls, U.S. Deputy Surveyor.
 Original Corner; Sugar Wood Post
 Original Bearing Trees:

| | | | |
|----------|-----|---------|---------------------|
| Ironwood | 4" | S 31° W | 37 lks (24.42 feet) |
| Sugar | 18" | N 70° E | 41 lks (27.06 feet) |

In January, 1963, C.C. Lindgren, MDOT, found an 1 1/4" axle shaft at ground level marking corner position, recorded in Liber 2, Page 269 of L.C. records.

1963 Bearing Trees:

| | | | |
|----------|-----|---------|------------|
| Maple | 12" | N 80° W | 27.18 feet |
| Basswood | 5" | N 30° E | 28.92 feet |
| Baswood | 4" | S 50° W | 32.70 feet |

In 1986, Gary L. Pisoni RLS found the above monument and set additional corner references:

| | | | |
|-----|-----|---------|------------|
| Ash | 9" | N 12° W | 14.52 feet |
| Ash | 10" | N 33° E | 28.92 feet |
| Ash | 6" | S 44° E | 19.08 feet |

PEER GROUP APPROVED
Iron County Rep 12-28-99
 COUNTY REPRESENTATIVE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of original B.T.s found.

On 4/22/99, found monument as described above and the following bearing tree:

| | | | |
|-------|-----|---------|------------|
| Maple | 20" | N 76° W | 26.99 feet |
| Ash | 11" | N 12° W | 14.52 feet |
| Ash | 12" | N 33° E | 28.92 feet |
| Ash | 8" | S 44° E | 19.08 feet |

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position, I replaced the axle shaft with a 2" diameter by 30" long split base aluminum pipe monument, with a 3" dia. aluminum cap stamped as follows: Iron County Remonumentation, T43N, R32W, S-28, S-29, S-32, S-33, 1999, RLS 27457 from which I established the following new corner reference:

Steel sign post East 0.93 feet

99-92
 Signed by Gary L. Pisoni Date 12-28-99

Surveyor's Michigan License No. 27457

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS JAN. 28, 1971

