

RF

MAR 09 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Table with columns: Iron (County), Located in:, Corner Code #. Includes entries for Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

IRON COUNTY MICHIGAN RECEIVED FOR RECORD

99 DEC 30 AM 10:12
L.C. Records: L.S. P. 20
Richard J. Jelic
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

Quarter Corner Sections 21 and 28, T43N, R32W

I, Gary L. Pisoni, in a field survey on April 23, 1999, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

Grid table with columns A-M and rows 1-13. A dot is marked at the intersection of column F and row 9.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established on August 11, 1849 by Zelotes B. Searls, U.S. Deputy Surveyor.
Original Corner: Maple Post
Original Bearing Trees:

Table with columns: Tree Type, Diameter, Bearing, Distance. Includes White Pine and Yellow Pine.

PEER GROUP APPROVED

Iron Gary Pisoni 12-21-99
COUNTY REPRESENTATIVE

Corner shown monumented by a plat concrete monument marking the Southeast corner of the Great Western Plat of Crystal Falls and monument was set by Robert F. Perkins RLS in 1973.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of original B.T. s found.

On 4/23/99, found the above concrete monument in good condition and 6" below gravel surface, and no corner references found. Corner located in the NW corner of the Crystal Falls Cemetery.

Accepted the concrete monument as the best available evidence for restoring the corner position.

Corner record research on file with County Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set two witness corners for the concrete monument as the quarter corner, said witnesses being a 5/8" diameter by 30" long rebar with a 3" diameter aluminum cap stamped as follows: Iron County Remonumentation, T43N, R32W, R.M., 1/4, S-21, S-28, S 56° E, 46.48', 1999, RLS 27457 and Iron County Remonumentation, T43N, R32W, R.M., 1/4, S-21, S-28, N 26° W, 9.75', 1999, RLS 27457 from which the following bear: (All measurement taken to a nail in side of tree)

Table with columns: Monument Type, Dimensions, Bearing, Distance. Includes R.M., Red Pine, Utility Pole, Fire Hydrant, and Steel sign post.

99-20
Signed by Gary L. Pisoni Date 12-28-99

Surveyor's Michigan License No. 27457

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS JAN 28, 1971

