

MAR 09 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Iron</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>43N</u> R <u>32W</u>	<u>G-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

IRON COUNTY  
MICHIGAN  
RECEIVED FOR RECORD

99 DEC 30 AM 10:12  
L.C. Records: L.S. P. 23  
*Gary L. Pisoni*  
REGISTERED LAND SURVEYOR

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

Section Corner Sections 27, 28, 33, 34, T43N, R32W

I, Gary L. Pisoni, in a field survey on April 21, 1999, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11							●						
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established on August 25, 1849 Zelotes B. Searls, U.S. Deputy Surveyor  
Original Corner: Cedar Post  
Original Bearing Trees:

Yellow Pine	18"	S 61° W	53 lks (34.98 feet)
White Pine	24"	N 20° E	2 lks (1.32 feet)

PEER GROUP APPROVED

*Don Ray* 12-21-99  
COUNTY REPRESENTATIVE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found a large stump hole marking the Yellow Pine bearing tree at record bearing and distance.

Found a WMPCo 2 1/2" diameter galvanized iron pipe with a 3" diameter brass cap located at a fence corner which runs North and East, brass cap is 8" above ground surface.

I accept the above monument as the best available evidence for restoring the corner position.

Corner record research on file with County Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

From the above described monument which is stamped as WMPCo, T43N, R32W, S-27, S-28, S-33, S-34, I established the following blazed and scribed new bearing trees: (all measurements taken to a nail in side of tree)

Oak (multiple stem)	8"	S 84° E	80.35 feet
Red Maple	11"	S 32° W	75.01 feet
Oak	20"	N 88° W	58.11 feet
Red Maple	9"	N 47° W	46.90 feet
Iron Bar w/flat top		S 21° E	0.30 feet
Steel sign post		S 53° E	1.05 feet

99-23  
Signed by Gary L. Pisoni Date 12-28-99  
Surveyor's Michigan License No. 27457

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN 28, 1971  
No. 27457  
REVISED MAY 14, 1975  
REVISED JAN. 1983  
REVISED OCT., 1995

