

MAR 09 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Iron</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>43N</u> R <u>32W</u>	<u>K-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

IRON COUNTY
MICHIGAN
RECEIVED FOR RECORD
99 DEC 30 AM 10:18
L.C. Records: 1, 8, p. 54
[Signature]
REGISTER OF DEEDS
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Section Corner to Sections 11, 12, 13, 14, T43N, R32W

I, Gary L. Pisoni, in a field survey on October 5, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established on Aug. 4, 1849 by Zelotes B. Searls, Deputy Surveyor.
Original Corner; Spruce Post
Original Bearing Trees:

Hemlock	18"	S 54°E	17 lks (11.22 feet)
Yellow Birch	16"	N 54° W	22 lks (14.52 feet)

On 12/3/53, Murray S. Gates, RLS restored the corner position with a 1" diameter iron pipe. He set the iron pipe 5272 feet West of the Southeast corner of Section 12 and 5280 feet East of the iron pin located at the Southwest corner of Section 11, recorded in Liber 2, Page 27 of L.C. records. Iron pipe is on line between above corners. No evidence of original bearing trees were found.

PEER GROUP APPROVED
Iron County 12-31-99
COUNTY REPRESENTATIVE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of original B.T.s found.

Found a 1" diameter iron pipe, 24" long lying at an angle in the ground. Iron pipe is located on the East edge of a small clearing which has been used for a pulp landing. Also found a 1 1/4" diameter pipe which bears N 08°18'33"W and a distance of 50.81 feet from the 1" iron pipe.

I accept the 1" diameter iron pipe as the best available evidence for restoring the corner position.

Corner record research on file with County Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Over the top of the existing iron pipe, set a 2" diameter by 30" long split base aluminum pipe monument, with a 3" dia. aluminum cap stamped as follows: Iron County Remonumentation, T43N, R32W, S-11, S-12, S-14, S-13, 1999, RLS 27457 from which I established the following new blazed and scribed bearing trees:(All measurements taken to a nail in side of tree)

Black Spruce	7"	S 46° W	52.60 feet
Black Spruce	10"	N 18° W	16.49 feet
Black Spruce	8"	N 20° E	35.59 feet
Black Spruce	9"	N 88° E	35.44 feet
Steel sign post		N 70° W	0.65 feet

99-54
Signed by Gary L. Pisoni Date 12-28-99
Surveyor's Michigan License No. 27457

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS: JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983
REVISED OCT., 1995

