

MAR 09 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

_____ Iron _____ (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>43N</u> R <u>32W</u>	<u>K-10</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

IRON COUNTY
MICHIGAN
RECEIVED FOR RECORD

99 DEC 30 AM 10:19
L.C. Records: L. 8, P. 56
Robert Steles
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Quarter Corner to Sections 25 and 26, T43N, R32W

I, Gary L. Pisoni, in a field survey on September 7, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established on Aug. 27, 1849 by Zelotes B. Searls, Deputy Surveyor.

Original Corner; Cedar Quarter Post

Original Bearing Trees:

Cedar	10"	S 70° W	10 lks (6.60 feet)
Cedar	10"	N 51° E	7 lks (4.62 feet)

On 10/31/68, Edward Kazianka RLS restored the corner position from the existing original bearing trees, set a 1" diameter iron pipe, 36" long with a 4" diameter aluminum cap stamped as follows: Kimberly Clark Corporation, T43N, R32W, 1/4, S-25, S-26, 10/31/68, RLS 14765, recorded in Liber 2, Page 534 of L.C. records.

1968 Bearing Trees:

Cedar	6"	N 76° W	30.5 lks (20.13 feet)
Cedar	7"	S 84° E	19.5 lks (12.87 feet)

PEER GROUP APPROVED

Iron Co. Rep. 12-21-99

COUNTY REPRESENTATIVE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of original B.T.s found.

Found monument as described above, 12" above ground surface and the following bearing trees:

Cedar	10"	N 79° W	20.00 feet
Cedar	13"	S 82° E	13.19 feet

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Blazed and scribed the following new bearing trees: (All measurements taken to a nail in side of tree)

Cedar	9"	N 27° W	23.95 feet
Cedar	11"	S 12° W	13.36 feet
Steel sign post		S 48° W	0.84 feet

99-56

Signed by Gary L. Pisoni Date 12-28-99

Surveyor's Michigan License No. 27457

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971

REVISOR MAY 14, 1975

REVISOR JAN., 1983

REVISOR OCT., 1995

