

MAR 09 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Iron</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>43N</u> R <u>32W</u>	<u>K-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

IRON COUNTY
MICHIGAN
RECEIVED FOR RECORD

99 DEC 30 AM 10:12
L.C. Records: L. 8, P. 21

Richard Selles
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Section Corner Sections 25, 26, 35, 36, T43N, R32W

I, Gary L. Pisoni, in a field survey on April 21, 1999 do hereby state

that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established on August 28, 1849 by Zelotes B. Searls, U.S. Deputy Surveyor.

Original Corner: Spruce Post

Original Bearing Trees:

Spruce	4"	S 69° 30' W	46 lks (30.36 feet)
Tamarack	8"	N 45° E	43 lks (28.38 feet)

PEER GROUP APPROVED

Gary Pisoni 12-21-99

COUNTY REPRESENTATIVE

On 4/20/76, Arthur Enger RLS found a 1" diameter by 63" iron pipe marking the corner position located in a spruce swamp. Position is consistent with other corners in the area. He replaced the iron pipe with a 1" by 36" long iron pipe with a 3 3/4" aluminum cap stamped as follows: T43N, R32W, S-25, S-26, S-35, S-36, 4-20-76, RLS 13581, and recorded in Liber 1, Page 470.

1976 Bearing Trees:

White Pine	20"	S 79° W	101.1 feet
Tamarack (dead)	6"	S 84° E	24.2 feet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of original B.T. s found.

On 4/21/99, found monument as described above. The above White Pine was wind thrown.

I accept the above monument as the best available evidence for restoring the corner position.

Corner record research on file with County Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Blazed and scribed the following new bearing trees: (all measurements taken to a nail in side of tree)

Black Spruce	3"	N 51° E	11.77 feet
Black Spruce	4"	S 31° E	40.97 feet
Cedar	8"	S 72° W	83.40 feet
Black Spruce	3"	N 46° W	54.24 feet
Steel sign post		North	0.77 feet

99-21

Signed by Gary L. Pisoni

Date 12-28-99

Surveyor's Michigan License No. 27457

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971

REVISED MAY 14, 1975

REVISED JAN., 1983

REVISED OCT., 1995

