

MAR 09 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Iron</u> (County)	Located In:	Corner Code #	
1. Public Land Survey	T <u>43N</u> R <u>32W</u>	<u>M-5</u> ✓	
	T <u>43N</u> R <u>31W</u>	<u>A-5</u>	
	T _____ R _____	_____	
	T _____ R _____	_____	
2. Property Controlling in Section	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	

IRON COUNTY
MICHIGAN
RECEIVED FOR RECORD

99 DEC 30 AM 10:11
L.C. Records: L. 8, P. 18

Gary L. Pisoni
REGISTERED LAND SURVEYOR

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Section Corner Section 12 and 13, T43N, R32W
Section Corner Section 7 and 18, T43N, R31W

I, Gary L. Pisoni, in a field survey on April 23, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2			1
3													
4		7		8		9		10		11			12
5													
6		18		17		16		15		14			13
7													
8		19		20		21		22		23			24
9													
10		30		29		28		27		26			25
11													
12		31		32		33		34		35			36
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established in 1846 by William A. Burt, U.S. Deputy Surveyor.

Original Corner: Cedar Post

Original Bearing Trees:

Cedar	12"	S 42°E	16 lks(10.56 feet)
Cedar	14"	N 45°W	13 lks(8.58 feet)

On July 28, 1849, John Burt, U.S. Deputy Surveyor, made a new bearing tree:

Cedar	12"	N 20°E	20 lks(13.20 feet)
-------	-----	--------	--------------------

On 09-23-52, Dean C. DeLameter, R.L.S., set a 1" pipe with a 4" diameter brass cap at original corner position. Found one original B.T. in place, down, and good condition. G. Divine, District Forester of Crystal Falls pointed out the original evidence, said monument stamped as follows: Michigan Dept. of Conservation, T43N, S-12, S-7, S-13, S-18 and recorded in L.2, page 9.

1952 Bearing trees:

Cedar	6"	East	64 lks.(42.24 feet)
Cedar	6"	N 25°E	14 lks.(9.24 feet)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

On 4-23-99, found monument as described above and the following bearing trees by unknown person:

Cedar	15"	N 21°E	9.85 feet
Cedar	16"	S 85°E	42.24 feet
Cedar	12"	N 83°W	15.70 feet

Corner record research on file with County Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set two (2) new corner references:

Utility Pole (Remains of Pole Butt)	S 10°W	41.42 feet
Steel sign post	North	0.57 feet

99-18
Signed by Gary L. Pisoni Date 12-28-99

Surveyor's Michigan License No. 27457

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY, 1975
REVISED JAN., 1983
No. 27457 REVISED OCT., 1995

