

MAR 09 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Form with fields for Iron (County), Located In: T 43N R 32W, Corner Code # M-9, and other survey details.

IRON COUNTY MICHIGAN RECEIVED FOR RECORD

99 DEC 30 AM 10:11
L.C. Records: L. 8, P. 16
[Signature]

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

Section Corner Section 24 and 25, T43N, R32W
Section Corner Section 19 and 30, T43N, R31W

I, Gary L. Pisoni, in a field survey on April 22, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

Grid table with columns A-M and rows 1-13, containing numbers 1-36.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established in August of 1846 by William A. Burt, U.S. Deputy Surveyor. Original Corner; Cedar Post

Original Bearing Trees: Cedar 7" S 76°E 15 lks(9.90 feet), Cedar 6" N 61°W 25 lks(16.50 feet)

On July 14, 1849, John Burt, U.S. Deputy Surveyor, made a new bearing tree: Cedar 12" N 65°E 22 lks(14.52 feet)

On 09-22-52, Dean C. DeLameter, R.L.S., restored corner position from the SE original B.T., still in place, in good condition. Set a 1" dia. pipe with a 4" brass cap and stamped as follows: Michigan Dept. of Conservation, T43N, S-24, S-19, S-25, S-30, and recorded in L.2, Pg.10.

1952 Bearing trees: Cedar 7" N 70°W 31 lks.(20.46 feet), Cedar 9" S 10°E 28 lks.(18.48 feet)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

On 4-22-99, found monument as described above and the following bearing trees:

Cedar 12" S 09°E 18.56 feet, Cedar 13" N 71°W 21.09 feet

Corner record research on file with county representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Blazed and scribed the following new bearing trees: (All measurements taken to a nail in side of tree)

Cedar 8" N 51°E 27.06 feet, Cedar 9" S 31°W 13.04 feet, Steel sign post North 0.70 feet

99-16 Signed by Gary L. Pisoni Date 12-28-99
Surveyor's Michigan License No. 27457

PEER GROUP APPROVED
Iron County Rep 12-21-99
COUNTY REPRESENTATIVE

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN 28, 1972

