

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Iron</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 43N R 32W	L12
	T 43N R 32W	K12
	T _____ R _____	_____
	S _____ T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Apr 05 2005

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(L12) Center of Section 36. Not established in the original survey. 1976: A.O.Enger, RLS monumented the corner position at the intersection of straight lines connecting opposite Quarter corners.
 (K12) Quarter corner common to Sections 35-36. 1974: Reestablished by A.O.Enger, RLS midway and on line between Section corners 39.926 ch. North and South. Set 1"IDx36" Iron pipe with 3.5" aluminum cap. Cedar 6 S71E 14.8', Cedar 6 S12W 14.7'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(L12) Recovered but did not accept the 1976 monument. The 1976 position was established using an incorrect position for the Quarter corner common to Sections 25 and 36. The original GLO position for that Quarter corner now having been remonumented, the position for L12 is reestablished at the intersection of straight lines connecting opposite quarter corners. The 1976 monument was recovered 1.8' SW of the position described herein. The 1976 monument was destroyed. The 1976 witness trees were not recovered.
 (K12) Recovered the 1976 monument in good condition and at record bearing and distance from the 1976 witness trees, both in good condition. The scribe marks on the Cedar SE are visible. The blazes on the Cedar SW are overgrown. Left the monument in place and made new witnesses.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(L12) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nails in: 4" Spruce N10W 60.5' mrkd "C1/4 BT" 6" Poplar S66E 13.3' do 4" Oak in clump S63W 86.9' do 3" Spruce N62W 85.7' do Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with MDNR tag.	(K12) Fd. 1"IDx32" I.pipe with 3.5" alum. MDNR cap. Set measuring nails in: 7" Cedar S69E 15.1' marks visible 7" Cedar S13W 14.8' old blazes 7" Cedar N80W 26.5' mrkd "1/4S NBT" 6" Cedar N67E 8.8' do Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with MDNR tag.
--	---



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 4/7/05