

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Iron	Located In:	Corner Code #
(County)		
1. Public Land Survey	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
	S ___ T ___ R ___	_____
2. Property Controlling in Section	S 36 T 43N R 32W	2
	S 36 T 43N R 32W	5
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Apr 06 2005

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- (2-Sec. 36) East 1/16 corner between Sections 25 and 36. Not established in the original survey.
- (5-Sec. 36) North 1/16 corner, Section 36. 1976: A.O.Enger, RLS monumented the corner position midway and on a straight line between the Center of Section to the South and the Quarter corner to the north.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (2-Sec. 36) Established the corner on the Section line between Quarter corner 1313.86' West and Section corner 1313.86' East.
- (5-Sec. 36) Recovered but did not accept the 1976 monument. The 1976 positions for the Center of Section and North Quarter corner of Section 36 are deemed erroneous and have now been remonumented. I reestablished the 1/16 corner position midway and on a straight line between these two remonumented corners, which are 1321.76' north and south. The 1976 monument, which was recovered 2.9' SW of the corner position established, was removed.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|--|--|
| (2) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nails in:
10" Cedar N70E 47.8' mrkd "1/16S BT"
11" Cedar S58E 35.8' do
9" Cedar S16W 79.0' do
6" Maple in clump S81W 61.0' do
Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with MDNR tag. | (5) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nails in:
12" W.Spruce S23W 12.5' old blazes *
9" R.Maple N75E 19.0' old blazes *
12" W.Spruce N75W 19.7' mrkd "1/16S BT"
7" B.Spruce N21W 34.2' do
Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with MDNR tag. * denotes 1976 witness tree |
|--|--|

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 4/7/05