

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Iron	Located In:	Corner Code #
(County)		
1. Public Land Survey	T 43N R 32W	I4
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 02/16/2010 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(I4) Quarter corner common to Sections 10 and 11. 2004 - Recorded under the Iron County Remonumentation Program by Gary L. Pisoni PS in Liber 11, Page 118 of LCR. Set 5/8" dia. x 48" rebar with 3" dia. alum. Iron Co. Remonumentation cap. Tamarack 8" N01E 53.72', Spruce 9" N28E 62.80', Tamarack 9" S16deg 57'E 275.53', Tamarack 5" S00deg. 38'W 239.03', Steel sign post N82E 0.85'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(I4) Found the 2004 monument of record, as described, in good condition, and at record bearing and distance from the 2004 Tamarack N01E NBT, steel sign post witness, and Spruce NE NBT, now a dead stub. The Tamarack NBTs SE and SW are in place and in good condition but no distance taken to them this date. Left the monument in place and added one new witness.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(I4) Found 5/8" rebar with 3" alum. Iron Co. cap. Set measuring nail with MDNR tag in the side of: 3" Tamarack N53W 46.4' mrkd "1/4S NBT" Bearing is magnetic.



Signed by Stephan J. Szyszkoski Date 02/18/2010
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources and Environment, Office of Land and Facilities